

Development of Data Centre Design by Improving its Cooling Performance

Nur Hazlina binti Lamli, Nur Hazlina binti Lamli^{1*}, Samlisman a/l Choi Weng²

¹ Department of Civil Engineering (Building Services), Polytechnic Sultan Salahuddin Abdul Aziz Shah, Persiaran Usahawan, Seksyen U1, 40150 Shah Alam, Selangor, MALAYSIA

² Department of Civil Engineering (Building Services), Polytechnic Sultan Azlan Shah, Behrang Stesyen, 35950 Behrang, Perak, MALAYSIA

ABSTRACT

Data centre are rooms or facilities used to house and protect computer systems and vital information that being stored on servers located inside the main 'hall' of data centre. Research was conducted in the purpose of taking a measurement to see on how to make an improvements to its cooling performance. The research site with existing condition of 100m² facility consuming 1900MWh of electricity per annum and retrofitted original office space with no changes to existing façade or building cooling system. The method used was to improve heat-transfer performance by increasing the log-mean temperature difference (LMTD). LMTD describes the difference between the temperatures of the air passing across the coil fins and the water flowing through the coil tubes. Based on the data taken using a vane anemometer to measure the flow and temperature of the CRAC unit, the results indicates that by plotting a graph of log mean temperature difference versus variation of temperature, the result intersect at LMTD of 7.3. Data also indicates that, the key to designing a data centre are dependent on business model and the availability or uptime that we can get from dividing the Mean Time Between Failures (MTBF) with Mean Time Between Failures (MTBF) + Mean Time to Repair (MTTR). Using this formula, in maintaining the availability, redundancy and fault tolerance must be taken into account. Based on the Log-Mean Temperature Difference versus variation of temperature result, it proofs that by improving the data centre room conditions would have higher potential of increasing the cooling performance than the improving of HVAC unit.

Keywords:

Data centre design, Data centre availability and reliability, Space and design consideration, Energy efficient design

1. INTRODUCTION

Since the advent of the first computer, everyday life has become ever reliant on this technology to automate and make day to day tasks easier. In fact, data centres have become so integrated into society they have become invisible to the user.

When thinking about where computers are used, it can be seen that most activities do have a computer system somewhere in the process. Tasks such as making a purchase at the local supermarket using EFTPOS; or making a telephone call; then again, using the internet to find out what news is occurring around the world.

Each of these activities uses, in the background, a computer infrastructure called a DATA CENTRE.

The data centre is the core of all financial, telecômmunications, and internet organisations to name a few. Without the data centre, these organisations would not be able to provide the services that their clients have grown accustomed to.

The data centre is a specialised facility in which computer systems are housed. It is not enough to just provide a standard building. Essentially, personal details and potentially sensitive information is stored in data centres. The organisations which hold this information should have a duty of care to their clients and users to securely hold and maintain their records and information. As such the data centre facility must be secure.

It is also important that the computers housed in the data centre be available at any time of the day. This is so clients and users can have access to their information where ever and whenever they need it. Therefore, to provide this 24/7/365 service, the data centre cannot just rely on the electricity company to provide an uninterrupted power supply. As part of our studies in the design and development of data centres, the task of testing was undertaken on an existing facility of 100m² facility consuming 1900MWh of electricity per annum and retrofitted original office space with no changes to existing façade or building cooling system at Victoria University's Footscray Park Campus and to take measurements of the temperatures and air velocities at a number of key location within the facility.

2. METHODOLOGY

The experiment was conducted in Victoria University Footscray Park Data Centre. Figure 1 shows the layout for the present study. The floor area is 42m², equipped with 33 heat-dissipating racks, 4 CRAC units, and 3 UPS units. Table 1 describe the experimental conditions; heat loads in different racks and air velocity from different CRAC units supply. Three CRAC units are active during the experiment that supplies downward cooling airflow through the raised floor plenum acting as one big CRAC units to cool down the entire facility.

Footscray Park Data Centre Floor Plan




Figure 1: VU Footscray Park data centre floor layout

The dotted points are where all the measurements are taken during the experiment.

EXPERIMENT METHOD:




Figure 1: Thermocouple-based temperature measurement grid. All units are in mm.

1. The ambient temperature was measured in the middle of the room.
2. The temperature from the CRAC supply was measured from a three different spot.
3. Measured return grill temperature at three different spot.

4. Placed the layout grid at the designated racks. Take the measurement based on the grid.
5. Take air velocity for each racks and each point taken in process number 1 to 3.

3. RESULTS AND DISCUSSIONS

Table 1: Experimental condition result

RETURN AIR TEMPERATURE

RETURN AIR GRID	TEMP (°c)
R.A-1	22.0
R.A-2	22.1

AMBIENT TEMPERATURE AT ROW D

SECTION	TEMPERATURE (°c)
COLD AISLE	21.9
HOT AISLE	25
MIXING	22.5

UNDERFLOOR / SUPPLY

FRONT OF SUPPLY		
TOP		10.9
MIDDLE		10.9
FLOOR		11.1
AIR VELOCITY	5.7 m/s	

FRONT OF SUPPLY		
TOP		14.2
MIDDLE		12.7
FLOOR		15.6
AIR VELOCITY	6.0 m/s	

MIDDLE OF SUPPLY		
TOP		16.9
MIDDLE		17.2
FLOOR		15.6
AIR VELOCITY	3.4 m/s	

MIDDLE OF SUPPLY		
TOP		19.7
MIDDLE		19.7
FLOOR		18.9
AIR VELOCITY	4.0 m/s	

FARTHER OF SUPPLY		
TOP		14.6
MIDDLE		14.5
FLOOR		15.1
AIR VELOCITY	2.8 m/s	

FARTHER OF SUPPLY		
TOP		21.0
MIDDLE		20.8
FLOOR		20.6
AIR VELOCITY	3.3 m/s	

READING AT THE FRONT OF THE RACK SERVER RACK D3

FRONT OF SUPPLY		
TOP		23.3
MIDDLE		23.2
FLOOR		23.2
AIR VELOCITY	1.5-2.0 m/s	

READING AT THE BACK OF THE RACK SERVER RACK D3

FRONT OF SUPPLY		
TOP		25.7
MIDDLE		26.1
FLOOR		25.9
AIR VELOCITY	-	

READING AT THE FRONT OF THE RACK COMMS RACK A9

FRONT OF SUPPLY		
TOP		22.7
MIDDLE		22.5
FLOOR		22.5
AIR VELOCITY	-	

READING AT THE BACK OF THE RACK COMMS RACK A9

FRONT OF SUPPLY		
TOP		23.5
MIDDLE		23.9
FLOOR		24.2
AIR VELOCITY	-	

SITE ANALYSIS

Dynamic of Heat Transfer

The performance of current cooling system was measured by the application of the Log-Mean Temperature Difference (LMTD) value. LMTD describes the difference between the temperatures of the air passing across the coil fins and the water flowing through the coil tubes.

The following equations quantifies the heat-transfer process:

$$Q = U \times A \times \text{LMTD}$$

Where,

Q = amount of heat transferred, (W)

U = heat-transfer coefficient, (W/m² . K)

A = effective surface area for heat transfer, (m²)

LMTD = log-mean temperature difference across the coil surface, (°C)

The most effective way to improve heat-transfer performance is to increase the log-mean temperature difference (LMTD).

$$\text{LMTD} = (\text{TD}_2 - \text{TD}_1) / \ln . (\text{TD}_2 / \text{TD}_1)$$


Where,

TD₁ = leaving-air and entering-water temperature difference at the coil, (°C)

TD₂ = entering-air and leaving-water temperature difference at the coil, (°C)

Room condition:

ENTERING AIR TEMPERATURE (RETURN AIR) (°C)	24
LEAVING AIR TEMPERATURE (SUPPLY AIR) (°C)	10
ENTERING WATER TEMPERATURE (CHILLED WATER) (°C)	6
LEAVING WATER TEMPERATURE (HOT WATER) (°C)	12



Summary

The graph proves that improving the data centre room conditions would have higher potential of increasing the cooling performance than the improving CRAC unit.

4. CONCLUSIONS

Overall, this research has provided an overview of requirements that must be considered at an early stage of design. It is clear that, when it comes to building a reliable data centre and maximising the investment, various design issues must be studied and resolved early in the building development process. The process should involve coordinated efforts across a number of areas of expertise including mechanical, electrical, architectural and other building services.

To achieve satisfactory outcomes, each of the components of the data centre and its supporting systems must be carefully planned, designed and implemented to work together to ensure reliable performance of discrete data centre resources while also taking into account future requirements and provision for expansion. Neglecting any aspect of the design can render the data centre vulnerable to cost failures, early obsolescence, and intolerable availability. There is no substitute for careful planning and the following the guidelines set in the specified standards.

ACKNOWLEDGEMENT

We'd like to acknowledge the help of the following in providing information and guidance in developing this research:

Ray Garrata, Electrical Engineer, Lehr Consultants International (Australia PTY LYD)

Yogesh Raju, Electrical Engineer, Lehr Consultants International (Australia PTY LYD)

David Yip, IBM Data Centre Services Consultant, IBM Australia

Richard Jacewicz, Systems Manager; Operating Systems Group, IT Enterprise Services; Department of Information Technology Services, Victoria University

REFERENCES

- [1] U.S Dept of Energy, Best Practices Guide for Energy Efficient Data Center Design, [webdocument](2011)
<<http://www1.eere.energy.gov/femp/pdfs/eedatacenterbestpractices.pdf>>,
Accessed 19-03-2012
- [2] ALGER, DOUGLAS, Build the Best Data Centre Facility for Your Business (Indianapolis, USA : Cisco Press, 2005) <<http://www.iphelp.ru/faq/36/toc.html>>,
Accessed 19-03-2012
- [3] 'Requirements for a secure data centre', *SANS Institute*, (2002),
<http://www.sans.org/reading_room/whitepapers/recovery/requirements-design-secure-data-center_561>, Accessed on 30-3-2012
- [4] 'Introduction to the New Mainframes: z/OS Basics', *IBM*, 2006,
<<http://publibz.boulder.ibm.com/zoslib/pdf/zosbasic.pdf>>, Accessed 16-May-2012
- [5] 'The Four Trends Driving the Future of Data Centre Infrastructure Design and Management', *Emerson Network Power*, (2012),
<<http://www.datacenterknowledge.com/archives/2012/04/24/the-four-trends-driving-the-future-of-data-center-design/>>, Accessed 16-May-2012
- [6] The MERV Rating System for Air Filters (Definition of MERV) [web page],
<<http://www.ontimeairfilters.com/air-filter-merv-rating>>, Accessed 16-May-2012
- [7] Fire suppression systems 'Fire Suppression Protection', *Fire Protection/System* [web page](2004) <<http://www.globalcenter.net.au/info/virtour/fireprotect.php>>
accessed on 1 Apr. 2012.
- [8] Threat Management in the Data Centre, 'Threat Management in Data Centres', How to and where to use sensors [web page] (2012)
<http://www.on365.co.uk/Data_Centres/Threat_Management_in_the_Data_Centre.aspx> accessed on 13 Apr. 2012.
- [9] Water leak detection system 'Water Leak Detection System', *Types of water leak detection system* [web page] (2005) <<http://www.alpha-plumbing.com/water-leak-detection-systems.htm>>, accessed on 15 May 2012.
- [10] Karen Kroll- May 2007, 'Fighting Fires in Data Centres': Fighting Fires In Data Centres, *Facilitiesnet* [online journal],
<<http://www.facilitiesnet.com/datacenters/article/Fighting-Fires-in-Data-Centers--6657>> accessed on 1 Apr. 2012,

- [11] Taking a planned approach to data centre fire prevention, viewed on 1st April 2012,
<http://xtralis.com/resources/article_level1/836/a_asr_Data_Centre_Fire_Prevention_Feature_Story.pdf>
- [12] Fire Hazards in Computer Rooms and Data Centres, viewed on 1st April 2012,
<http://www.verst.com.au/pdf/APF_understanding_fire.pdf>
- [13] Determination of Standard Response Spectra and Effective Peak Ground Accelerations for Seismic Design and Evaluation by Enrique E. Matheu, Don E. Yule, and Raju V. Kalahttp: <<http://www.dtic.mil/cgi-bin/GetTRDoc?AD=ADA441347>> accessed 15 May 2012.
- [14] ASHRAE Datacom Series 1, Thermal Guidelines for Data Processing Environments, (2nd Ed.; Atlanta, GA, 2009)
- [15] ASHRAE Datacom Series 6: Best Practices for Datacom Facility Energy Efficiency, (2nd Edn.; Atlanta, GA, 2008)
- [16] Reliability and Availability Basics [web page],
<http://www.eventhelix.com/realtime mantra/fault handling/reliability_availability_basics.htm>, accessed 20 May 2012
- [17] Speaks, S., Reliability and MTBF Overview, *Vicor Reliability Engineering*, [web document], <http://www.vicorpower.com/documents/quality/Rel_MTBF.pdf>, accessed 20 May 2012
- [18] io Data Centres, *Financial Services* [web page] (2007-2012)
<<http://www.iodatacenters.com/data-center-colocation-solutions/industry/financial-services>>, accessed 21 March 2012
- [19] [web page] <<http://www.videocontrolroom.com/home.php>>, accessed 23-5-12
- [20] [web page] <<http://ipadfanzz.blogspot.com.au/2011/04/logitech-s-new-security-app-allows.html#!/2011/04/logitech-s-new-security-app-allows.html>>, accessed 24-5-12
- [21] [web page] <<http://www.directindustry.com/prod/bioacez-controls/biometric-sensors-fingers-veins-readers-39706-396431.html>>, accessed 24-5-12